

Tender Enquiry

Ref. No. ITI/RB/CS/2024/7315

Date: 19.11.2024

M/s

(Must be fill by the agencies)

Subject:- One time maintenance and operation of 1.5 MW solar PV plant installed at Raebareli.

Dear Sir,

Bid offers in **two envelope for technical and financial** separately are invited on behalf of ITI Limited Raebareli from experienced service providers in the relevant field for the subject work and prospective bidders are requested to submit their offer through offline, as per terms and conditions stipulated below:-

Tender Submission due date: 29/11/2024 upto 5:00 pm

ELIGIBILITY CRITERIA FOR BIDDER:

1. Bidder should have experience for similar kind of work (supply and maintenance of Grid tied solar power plant) and required to submit the experience certificate for similar work from reputed PSU/Govt or any reputed private organization during the last 03 years.
2. The Average Annual financial turnover of the firm should be at least 10 Lacs during the last 03 consecutive financial years ending 31-03-2024. Copies of duly attested statement (for last 03 years) by Chartered Accountant should be provided.
3. Bidders are requested to submit supportive documents for GSTIN Registration, PAN Registration.
4. **EARNEST MONEY:** - ₹ 8,000.00 through DD/bankers cheque in favour of "ITI Limited Raebareli"; It will be returned to unsuccessful bidder after the finalization of the tender. EMD will be forfeited who backs out or is found to be providing misleading information during tendering process. Registered with MSME are exempted from earnest money deposit.
5. Compliance/signed copy to our tender terms and conditions.
6. In absence of any above documents, the bid/offer may be rejected.
7. The Price Bid: Rates, GST and amount should be clearly filled in the sheet in the tender document and submitted in separate envelope.




CM-CS&CIVIL

Signature and Stamp of contractor

Salient Terms and conditions of the tender

1. **SCOPE OF WORK:-**As per enclosed Annexure-I,
2. This is only an enquiry to quote and not an order. This tender enquiry is not transferable
3. **Tender opening date: 30/11/2024**
4. Tenders must be submitted at CM (Civil & CS), Central dispatch-ITI limited, Sultanpur Road Raebareli 229010 through registered post.
5. **CONTRACT PERIOD:** - The Contract period will be 01 month from the date of award of work order & it may be extended, if required, on mutual consent for a period of One month's maximum.
6. **PAYMENT TERMS:** - 100% payment will be made after successful completion of work through electronic fund transfer.
7. The workers engaged by the contractor shall strictly observe factory discipline.
8. **LD CLAUSE:** - LD @ Rs 500/ day will be applicable beyond due delivery period (i.e 01 month) and It will be maximum upto 10% of work order value .LD will be recovered from the submitted bills. In case of poor & unsatisfactory services, contract may be terminated and the party may be barred from any further dealing with ITI.
9. **TAXES DEDUCTIONS:-**It will be applicable as per govt. rules.
10. The work shall commence immediately on issue of Work Order as per the Work Order conditions.
11. Actual payment will be made as per verification of the work.
12. All tools and tackles will be arranged by the Contractor for execution of the work.
13. The contractor shall take necessary safety measures to ensure safety of personnel, ITI property and equipment's while discharging duties.
14. The Contractor will indemnify ITI ltd from losses /damages cause to ITI Ltd by his persons or by negligence of them, and the same may be recovered from the running bill if not indemnified within stipulated time.
15. Other standard terms and conditions of ITI Ltd are also applicable without any prejudice.
16. **Prospective bidders are advised to visit the site and assess the scope of work before submitting the bid.**
17. Dispute if any will be under jurisdiction of RaeBareli UP judicature.
18. The list of personnel engaged for the work will be intimated in advance and they will be allowed to enter inside the premises of the ITI Ltd with proper ID proofs. The contractor will not engage any regular, contract employees or contract laborers of the ITI Ltd for carrying out the work.
19. ITI Ltd reserves the right to accept or reject any bid, and to annul the bidding process and reject all bids, at any time prior to award of contract without assigning any reason whatsoever and without there by incurring any liability to the affected bidder or bidders on the grounds of ITI Ltd action.
20. Tender documents can be downloaded from ITI website and CPPP portal
21. ITI Limited will not be responsible for non-receipt/late receipt of tender document after the last date of submission.

Tender Submission Last date: 29/11/2024 upto 5:00 pm



CM-CS&CIVIL

Signature and Stamp of contractor

Annexure 1

Scope of works

Sub: - One time maintenance and operation of 1.5 MW solar PV plant installed at ITI Limited Raebareli.

S.No	Description of works	QTY
1.	Checking and restoring DC string voltage (800V) at each SMB terminal and rectify /replace MC4 connector and insulation of cable if damaged	1 JOB
2.	Checking each bus bar in ACDB Panel and rectify/replace 02 Nos faulty busbar including insulators and taping etc	
3.	Checking each on load isolator and rectify/replace 01No. on load isolator	
4.	Checking and rectify/replace 01 set of fuse wire , fuse & insulator of HT Breaker	
5.	Checking & restore earthing of the items	
6.	Miscellaneous maintenance works as per site requirement if required	

List of items installed at solar site as mentioned below:

S.No	List of items	Qty	Make
1.	SMB (String monitoring box)	15	NA
2.	Inverter(100KW)	15	DELTA
3.	ON-Line isolator switch	15	NA
4.	LT breaker (2500A)	01	L&T
5.	Transformer (2.5 MVA)	01	Mahendra transformer limited
6.	HT breaker (800A)	02	Schneider



CM-CS&CIVIL

Signature and Stamp of contractor

PRICE BID

Sub: - One time maintenance and operation of 1.5MW Grid tied solar PV installed at ITI Limited raebareli

S.No	Description of works	QTY	Quoted rate
1.	Checking and restoring DC string voltage (800V) at each SMB terminal and rectify /replace MC4 connector and insulation of cable if damaged	1 JOB	Basic value:.....
2.	Checking each bus bar in ACDB Panel and rectify/replace 02 Nos faulty busbar including insulators and taping etc		GST@.....%=.....
3.	Checking each on load isolator and rectify/replace 01No. on load isolator		Total Value=.....
4.	Checking and rectify/replace 01 set of fuse wire , fuse & insulator of HT Breaker		
5.	Checking & restore earthing of the items		
6.	Miscellaneous maintenance works as per site requirement if required		



CM-CS&CIVIL

Signature and Stamp of contractor