



ITI Limited
MSP-Kerala
Pattathil Building, First Floor
Vidhya Nagar, Panampilly Nagar
Kadavanthara P.O.
Kochi-682 020.
CIN No: L32202KA1950GOI000640

Tender No: MSP-Kerala/EOI-104(20-21)

Date: 19/10/2020

ITI Limited Invites Tenders against Tender No: MSP-Kerala/EOI-104(20-21) Closing Date: 19/10/2020 2.00 PM, as per the attached Bill of Materials.

Due Date for Submission of tender is 31/10/2020 before 2.00 PM.

A	Technical Bid	
1	Scope of Work	Supply and labour works for Telephone line cabling work
2(i)	Eligibility Criteria of Applicants	
	A.	-NA-
	B.	The bidder must be registered / incorporated under Indian Companies Act, 1956 or other relevant Act/Rules and should have a base in India for at least three years.
	C.	-NA-
	D.	-NA-
	E.	Bidder should have an average turnover of Rs.15 lakhs during the last 3 financial years. Audited statements to be furnished.
	F.	The Bidder should have executed similar projects during the last seven years. Documentary evidence such as Purchase Order copies and completion certificates to be furnished, especially from Government Agencies / PSUs. List of projects done in Kerala State from Govt. Agencies to be submitted. Bidders having experience in Kerala State are preferred.
2(ii) Checklist of documents/information to be submitted:		
a.	Company Profile	
b.	Certificate of Incorporation	
c.	Memorandum & Articles of Association	
d.	Audited financial statements for the last 3 years. (2016-17, 2017-18 & 2018-19) and CA certificate.	
e.	Positive Net Worth Certificate (2016-17, 2017-18 & 2018-19).	
h.	GST Registration Certificate.	
i.	Copy of PAN Card	
j.	CIN (Corporate Identity Number), if applicable	
k.	Authorization letter in the company letterhead authorizing the person signing the bid for this EOI and Power of Attorney (POA)	
o.	Supporting / Compliance documents as per 2(i) A,B,C,D,E,F,G	

Note:

1. Technical bids will be opened on **31/10/2020 at 3.00 PM.**
2. **The bids each page should be serial numbered.**
3. Conditional offers are liable for rejection.
4. Payment to the successful bidder shall be made after completion of Supply /Services within 45 days. (Penalties if any levied by the customer will be passed on to the Successful bidder). For Services 5% of bill amount will be deducted and paid after acceptance from the customer.
5. ITI will not consider any or all of the bids, if they are not meeting Tender requirements.
6. Prices to be quoted on F.O.R Trivandrum basis.
7. Make of cables – Finolex only.
8. Total categories of works are 6 nos as per Annexures. Prices to be quoted individually for all the 6 categories.

The Bid may be sent in a sealed cover mentioning that–

**“Tender for Supply and labour works of Telephone line cabling work in Kerala.
Tender No. MSP-Kerala/EOI-102(20-21) Date: 19/10/2020**

and to be submitted to the following address on or before 2.00 PM on 31-10-2020.

**Deputy General Manager
ITI Limited, MSP-Kerala
Pattathil Building, First Floor
Vidhya Nagar, Panampilly Nagar
Kadavanthara P.O.
Kochi-682 020.
PhNo. : 0484-2967601
Mob-99165 99219.
Email ID: udaya_nsu@itilttd.co.in.**

Sl.No.	Description of Supply- 1	Unit	Quantity.	Rate	Amount
1	0.5mm dia,100 pair Jelly filled armoured U/G Cable	Mtr	650.00		
2	0.5mm dia,100 pair PVC Cable	Mtr	120.00		
3	0.5mm dia., 2 pair PVC Cable	Mtr	500.00		
4	B Class GI Pipe 40 mm	Mtr	50.00		
5	200 pair Metal type Krone Junction Box with 100 pair SS back mount metal frame	Set	1.00		
6	100 pair Metal type Krone Junction Box with 100 pair SS back mount metal frame	set	1.00		
7	100 pair SS back mount metal frame	set	4.00		
8	10 pair Krone disconnection module	set	50.00		
9	32mm PVC pipe (Ivory ISI standard)	Mtr	120.00		
10	25 mm PVC pipe (Ivory ISI standard)	Mtr	400.00		
11	0.5 mm Jumper wire	Mtr	200.00		
12	U/G Telephone Cable Route marker	Nos.	20.00		
13	Telephone Instrument Make Panasonic Model KXTX500MX	Nos.	200.00		
14	RJ11 Rosette Box	Nos.	200.00		
15	GD Tube(10 nos.) plus magazine for 10 pair module	Nos.	40.00		
16	FCBC Dyna 48V 37.5 Amps(DY6350)	Nos.	1.00		
17	UPS system 600 VA	Nos.	1.00		
18	Multi function Printer(copy, scanning and printing)Canon	Nos.	1.00		
19	Personnel Computer System with Processor: Core i5,2.2gh, HDD:1TB, RAM: 8 GB, Monitor: 20" LED, Operating system ; Windows 10 original , Anti virus protection for three years	set	1.00		
	Total				
	GST@18%				
	Grand total				

SI.No.	Description of supply-2	Unit	Quantity	Rate	Amount
1	Supply of GD Tube(10 nos.) plus magazine for 10 pair module	set	20.00		
2	100 pair SS back mount metal frame	set	2.00		
3	10 pair Krone disconnection module	set	20.00		
4	Supply of 0.5mm 20 pair PVC telephone cable	mtr	50.00		
5	Supply of 0.5mm 50 pair PVC telephone cable	mtr	170.00		
6	Supply of 0.5mm 10 pair PVC telephone cable	mtr	200.00		
8	Supply of Rosette Box	No	60.00		
	Total				
	GST@18%				
	Grand total				

Sl.no.	Description of supply-3	Unit	Quantity	Rate	Amount
1	Supply of 16 SWG GI Wire	Kg	6.00		
2	Supply of 4 way coil cord	nos	200.00		
3	Supply of 2 way coil cord for push button Telephone	nos	200.00		
4	Supply of Rosette Box	nos	200.00		
5	Supply of 0.5 mm 2 pair PVC telephone cable	nos	1550.00		
	Total				
	GST@18%				
	Grand total				

SI No	Description-Labour work/supply-1	Unit	Quantity	Rate	Amount
1	Trenching with 60cm depth X 30cm width, laying of 100 pair Jelly filled armoured U/G cable and filling the trench	mtr	460		
2	Tile cutting, Trenching with 60cm depth X 30cm width, laying of 100 pair Jelly filled armoured U/G cable and filling the trench	mtr	160.00		
3	Tar Road cutting, Trenching with 60cm depth X 30cm width, laying of 100 pair Jelly filled armoured U/G cable and concreting cut portion of Tar road	mtr	50.00		
4	Fixing charges for 100 pair pvc cables through wall in 32 mm PVC pipe including cost of accessories and fittings	mtr	120.00		
5	Fixing of 100 Pair Back metal frame and Termination of 100 pair U/G Cable in the frame	Set	1.00		
6	Fixing of 200 pair junction box and termination of 100 pair UG Cable including cost of fittings and accessories	Set	1.00		
7	Fixing of 100 pair junction box and termination of 100 pair UG Cable and 100 PVC cable in the Krone box including cost of fittings and accessories	Set	1.00		
8	Laying charges for 2 pair pvc cables through wall in PVC pipe including cost of accessories and fittings	mtr	400.00		
9	Termination of Rosette Box and Telephone instrument and testing of telephone lines	nos	100.00		
	Total				
	GST @18%				
	Grand total				

SI No	Description-Labour work/supply-2	Unit	Quantity	Rate	Amount
1	Laying of 0.5 mm 2 pair cable thru 20 mm PVC pipe including cost of pipe, fitting, accessories and labour charges	mtr	1200		
2	Laying of 10 pair cable thru 20 mm PVC pipe including cost of pipe, fitting, accessories and labour charges	mtr	50.00		
3	Laying of 10 pair cable thru 20 mm PVC pipe including cost of pipe, fitting accessories and labour charges	mtr	200.00		
4	Laying of 50 pair cable thru 25 mm PVC pipe including cost of pipe, fitting, accessories and labour charges	mtr	170.00		
5	supply , fixing and termination of 10 pair Krone box with module	Set	1.00		
6	supply , fixing and termination of 20 pair Krone box with module	Set	5.00		
7	Termination of Rosette Box and Telephone instrument and testing of telephone lines	nos	75.00		
	Total				
	GST@18%				
	Grand total				

SI No	Description-Labour work/supply-3	Unit	Qunatity		
1	Laying of 0.5 mm 2 pair cable thru 20 mm PVC pipe including cost of pipe, fitting accessories and labour charges	mtr	1250		
2	Laying of 10 pair cable thru 20 mm PVC pipe including cost of pipe, fitting accessories and labour charges	mtr	140.00		
5	supply , fixing and termination of 10 pair krone box with module	Set	5.00		
6	supply , fixing and termination of 20 pair krone box with module	Set	3.00		
	Total				
	GST@18%				
	Grand total				