

		GOVERNMENT OF INDIA				
		ITI LIMITED (PLANT ELECTRICAL DEPARTMENT)				
		BANGALORE PLANT				
		DOORVANI NAGAR BANGALORE 560016				
		Commercial Bid for Electrical works in IGI/IGA stores				
ENQUIRY NO / DATE:		ITI/BGP/CS/2023/IGA/ ELEC/Tender	DUE DATE:	13.10.2023 @ 11 pm	QUOTATION REFERENCE / DATE	
NAME OF THE SUPPLIER						
FULL ADDRESS :						
TEL NO. & MOBILE NO:						
e-MAIL ID :						
GST #:						
MSME UDYAM REGISTRATION REFERENCE:						
SL.NO.	ITEM DESCRIPTION	UNIT	QTY	Rate (Rs)	Amount(Rs)	
1	Supply & Installation testing of 600 x600x 3 mm Thickness Copper earth station with 48 mm x 2500 mm GI pipe with 2 Run 25 x 3 mm copper earth strip from Bottom earth plate to floor level, Excavation of pit with suitable quality of Salt & Charcoal,, Soil back Filling & providing the brick work with plastering, a with 450 x 450 mm CI Chamber cover					
	Supply	No's	2			
	Installation	No's	2			
2	Supply & Installation of 1+1, 20 amps Switch, Socket, Back Box & Front plate. Make : Anchor,Havells,Goldmedal					
	Supply	Set	6			
	Installation	Set	6			
3	Supply & Installation of Lighting Point wiring with using the 2 run x 1.5 sq mm +1 run x 1.5 sq mm Earth wire with require PVC Conduit pipe , Junction box, Bend collar etc.					
	Supply	No's	22			
	Installation	No's	22			
4	Supply & Installation of 2 ft x 2ft Grid / Surface LED fitting with fixing supports. Make: Philips,Syska,Crompton					
	Supply	No's	12			
	Installation	No's	12			
5	Supply & Installation of 4 ft LED light fitting. Philips,Syska,Crompton					
	Supply	No's	10			
	Installation	No's	10			

6	Supply & Installation of 2+2, 20 amps Switch, Socket. Make: Anchor, Havells, Goldmedal				
	Supply	No's	20		
	Installation	No's	20		
7	Supply & Installation of 12 way VTPN DB with incoming 63 amps 4 pole MCB & Out going 10/16/20 amps SP MCB's Make : Legrand / ABB/ Schindler (AC & Lighting DB)				
	Supply	No's	2		
	Installation	No's	2		
8	Supply & Installation of Power Point Circuit wiring with using the FRLHS 2 run x 2.5 sq mm +1 run x 2.5 sq mm Earth wire with require PVC Conduit pipe , Junction box, Bend collar etc. Wire : poly cab / havells/anchor				
	Supply	Mtrs	200		
	Installation	Mtrs	200		
9	Supply & Installation of Power Point Circuit wiring with using the FRLHS 2 run x 10 sq mm +1 run x 2.5 sq mm Earth wire with require PVC Conduit pipe , Junction box, Bend collar etc. Wire : poly cab / havells/anchor				
	Supply	Mtrs	200		
	Installation	Mtrs	200		
	Total				
	Total supply and Installation				
	GST 18%				
	TOTAL AMOUNT				